

SURVEY & REMONUMENTATION

AUG 06 2008

OSCODA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OSCODA (County) Located In: Corner Code #

- 1. Public Land Survey T26N R1E C-7
2. Property Controlling S T
3. Miscellaneous S T
Property in Sec. S T

APPROVED

County Remonumentation Peer Review Group

NOV 18 JULY 08

- 4. Lot No. Recorded Plat
5. Private Claims

I, Marvin E. Myers, P.S., in a field survey on Jan 10 20 08 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-7 Section Corner common to Sections 17, 18, 19, & 20 T26N-R01E.

1839 GLO William R. Coon Deputy Surveyor Mon.- Set post Corner Sections 19, 20, 17, 18 Wft: Aspen 8" S66 1/2°W 12 lks (7.92') Aspen 10" N46°E 31 lks (20.46')

Circa 1880's J Randall, CS

Mon - His notes indicate that he ran a line using this Corner as a beginning point. Wft: Not given

Continued on back of Sheet ->

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Section Corner common to Sections 17, 18, 19, & 20 T26N-R01E. Found a USGLO concrete monument with a brass cap in good condition, left in place and set 2 nails alongside the monument for magnetic attraction; N29°E 52.25' found a 10" White pine with a USFS location tag; S30°E 11.58' found a spike in the Southwest side of a 5" White pine with a USFS location tag; S08°W 2'± found Cedar post with a USFS location tag; S61°W 10.78' found a spike in the Southeast side of a twin 4" White pine with a USFS location tag; N08°45'W 43.56' found a 20" Norway pine stump. Accepted USGLO concrete monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Section Corner common to Sections 17, 18, 19, & 20 T26N-R01E. Mon - Found a USGLO concrete monument with a brass cap in good condition. Set 2 nails alongside the monument for magnetic attraction.

- Wft: N29°E 52.25' Found 10" White pine with USFS location tag and set N&T in Southeast side.
S30°E 11.58' Found spike in Southwest side of 5" White pine with USFS location tag.
S08°W 2'± Found Cedar post with USFS location tag.
S61°W 10.78' Found spike in Southeast side of 4" Twin White pine with USFS location tag.
N28°W 36.13' Set nail & tag in Southwest side of 10" White pine.
South 2'± Set Carsonite post.
North 12'± C/L of old East/West trail road.
West 3'± C/L of old trail bearing North.

OSCODA COUNTY REGISTER OF DEEDS 07/29/2008 09:33:00AM
FEE: \$17.00
PAGES: 2 RCPT#: 8285
LC8-144 CORNER RECORDATION

Register of Deeds Stamp & File Number

Table with 13 columns (A-M) and 13 rows (1-13) containing numbers and a dot in row 7, column C.



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600