

MAR 03 2000

LAND CORNER RECORDATION CERTIFICATE

SECTION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

1999 Alcona County Remonumentation

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|----------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 25N N. S., R. 5E E. W. | A-6 |
| 2. PROPERTY CONTROLLING IN SECTION | , T. _____ N. S., R. _____ E. W. | |
| 3. MISCELLANEOUS PROPERTY IN SECTION | , T. _____ N. S., R. _____ E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

Alcona County
Remonumentation
Liber 2 Page 12

U Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-17-1999 At 10:
LAND CORNER 9.00

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Dec. 8, 1999, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-6: 1838: GLO survey by L. Clason - set post and referenced
- 1905: survey by W. Chapelle - no description of corner
- 1929: dependent resurvey by G. Veal - set iron post 2" dia 3' long 40" in ground
- 1975: survey by N. Caldwell - no description of the corner

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date: 11/30/99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- A-6: nothing found at corner location which is in E-W county road
no evidence recovered from GLO survey of 1838

corner was established from 4" x 4" post with yellow Forest Service tag stating South 30.0 ft to corner, pagewire fence running South with Forest Service boundary sign, old fence running North and comparable distance and alignment from corners to the South

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-6: set 1/2" bar and aluminum cap in county road referenced:

- 11" maple / N 45°E / 21.48' to nail
- 4" x 4" post w. tag / North / 30.00 to center
- 5" cedar / South / 27.98' to nail
- 7" cedar / S 72°W / 68.05' to nail



SIGNED BY [Signature] DATE Dec. 8, 1999

John F. Oliver
SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____