

MAR 03 2000 LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

SECTION

1999 Alcona County Remonumentation

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>25N</u> N. S., R. <u>5E</u> E. W.	<u>A-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County Remonumentation Liber 2 Page 15

Filed for Record in ALCONA COUNTY MICHIGAN DORIS A GAUTHIER On 12-17-1999 At 10:32 LAND CORNER 9.00

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Dec. 8, 1999, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-9: 1838: GLO survey by L. Clason - set post and referenced 1929: dependent resurvey by G. Veal - set conc. mon. 6" x 24" with brass tablet

APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY Date 11/30/99 County Rep. [Signature]

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-9: found 6" x 24" conc. mon. with brass tablet no evidence recovered from GLO survey of 1838 no witnesses found from 1929 resurvey distances and alignment are compatible with 1929 dependent resurvey accepted as the correct location for the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9: 6" x 24" conc. mon. with brass tablet located in a low spot which is sometimes covered with water referenced: 10" oak / N 82°E / 149.43' to nail 13" maple / N 50°E / 148.42' to nail 8" dbl. maple / N 86°W / 84.32' to nail 6" maple / S 32°W / 107.78' to nail



SIGNED BY [Signature] DATE Dec. 8, 1999
John F. Oliver
SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____