

MAR 04 1998

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SECTION

1997 Alcona County Remonumentation

APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25N N. S., R. 5E E. W.	NW cor. S. 31 A-11
2. PROPERTY CONTROLLING IN SECTION	, T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO.	, RECORDED PLAT	
5. PRIVATE CLAIMS		

Date 7/24/97
 County Rep. D.A. Gauthier
 RECORDED
 Date Sept 8, 1997
 REMON LIBER 1 PAGE 250
 2:15 Time P M
Doris A. Gauthier
 Doris A. Gauthier
 REGISTER OF DEEDS
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Aug. 20, 1997, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. - set post and referenced
- 1906: E. Chapelle - gray boulder 12" x 14" with + on top - glass under
- 1929: Dependent resurvey - fd. stone - set 6" x 24" conc. mon w brass cap
- 1961: Scott Eng. - set nail and cap


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

fd. 1/2" bar - no cap - no accessories available
 accepted as true location of corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed aluminum cap stamped to identify the corner on 1/2" bar
 referenced: fence post / S 48°W / 52.20'
 fence post / N45°E / 43.02'
 double 6 & 11" cedar / N 60°W / 84.61'
 12" w. pine / S 40°E / 93.92'
 12" w. pine / N 75°E / 84.98'

SIGNED BY *[Signature]* DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 19840



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____