

MAR 04 1998

LAND CORNER RECORDATION CERTIFICATE

SECTION

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

1997 Alcona County Remonumentation

APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY

Table with 3 columns: FOR CORNERS OF--, LOCATED IN--, CORNER CODE NUMBER. Includes rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

Date 7/24/97, County Rec. [Signature], RECORDED Date Sept 8, 1997, REMON LIBER 1 PAGE 25, 2:15 Time P.M., Doris A. Gauthier REGISTER OF DEEDS, REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Aug. 20, 1997, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. - set post and referenced
1929: Dependent resurvey - fd. 1" dia pipe - set 2" iron post w brass cap
1961: Scott Eng. - fd. U.S. mon.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

fd. 1/2" bar - no cap - this bar is in line with fences East & West and falls very close to single prop. measure


no accessories found

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed pavement box with brass cap stamped to identify the corner on the 1/2" bar

- referenced: 13" w. pine / S 80°W / 61.68 ft
16" maple / East / 267.28 ft
fence post / East / 45.00 ft
fence post / West / 36.81 ft

SIGNED BY [Signature] DATE
SURVEYOR'S MICHIGAN REGISTRATION NO. 19840



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.