

MAR 03 2000

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

### SECTION

1999 Alcona County Remonumentation

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 25N N. S., R. 5E E. W.	C-5
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County  
 Remonumentation  
 Liber 2 Page 22

Filed for Record in  
 ALCONA COUNTY MICHIGAN  
 DORIS A GAUTHIER  
 On 12-17-1999 At 10:32 a  
 LAND CORNER 9.00

REGISTER OF DEEDS STAMP AND  
 FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Dec. 8, 1999, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-5: 1845: GLO sur. by J. Mullett - set post and referenced
- 1900: sur. by W. Chapelle - set cedar stake
- 1909: sur. by A. Freer - no identification
- 1931: dependent resur. by G. Veal - set 6" x 24" conc. mon. w. b. cap
- 1972: sur. by Caldwell (USFS) - fd. 1/2" bar and cap over USGLO mon.
- 1977: sur. by N. Caldwell - no description of corner

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-5: fd. 1/2" rod and cap over GLO mon.

no evidence recoverable from GLO survey of 1845


distances and alignment are compatible with surveys of 1931, 1972, and 1977

accepted as the correct location for the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5: placed 1/2" rod and aluminum cap referenced:

- 24" stone 10" high / N 80°W / 54.50 to center
- pow. pole / S 27°E / 88.44' to nail
- pow. pole / N 29°E / 115.68' to nail
- 7" birch / S 55°W / 38.12' to nail



APPROVED LAND CORNER  
 P A 345 of 1990  
 ALCONA COUNTY

Date: 11/30/99  
 County Rep [Signature]

Dec. 8, 1999

SIGNED BY [Signature]  
John F. Oliver

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_