

MAR 04 1998

SECTION LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970 RECORDED LAND CORNER P A 345 of 1990 ALCONA COUNTY

1997 Alcona County Remonumentation

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... T. 25N N. 55E E. W. W-1/4 cor. S. 17 C-6
2. PROPERTY CONTROLLING IN SECTION... T. N. S. R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION... T. N. S. R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

Date 7/24/97
County Rep. [Signature]
RECORDED
Date September 8, 1997
REMON LIBER 1 PAGE 260
Doris A. Gauthier REGISTER OF DEEDS
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Aug. 20 1997, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


- 1845: G.L.O. - set post and referenced
1933: Dependent resurvey - fd. wagon axle and old wooden stake - placed 6" x 24" conc. mon. w brass tablet
1976: N. Caldwell - no desc. of corner
1979: N. Caldwell - no desc. of corner

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

fd. 1/2" bar and cap with 6" x 24" conc. mon. with brass tablet with wagon axle and old wood stake along side, below the 1/2" bar and cap.
no accessories found

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed pavement box over Dependent resurvey monument
referenced: 14" cedar / N 25°W / 81.97 ft
power pole / N 30°E / 102.28 ft
14" double elm / S 70°E / 123.29 ft
13" spruce / S 50°W / 49.36 ft



SIGNED BY [Signature] DATE 9-8-97
SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_
CHIEF OF SURVEY PARTY
APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_