

MAR 04 1998

SECTION LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

1997 Alcona County Remonumentation

APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY

Date 7/28/97 County Rep. J.D.B.

RECORDED

Date September 8, 1997 REMON LIBER 1 PAGE 257

2:20 Time P.M. Doris A. Gauthier REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER NW cor. S. 20 C-7

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above... field survey on Aug. 20, 1997...

A. Description of original monument and accessories and/or subsequent restoration:

- 1845: G.L.O. - set post and referenced
1900: W. Chapelle - set stone marked X
1933: Dependent resurvey - fd. wood post - set 6" x 24" conc. mon. w brass cap
1973: R. Miller - no desc. of corner
1991: Rowe Eng. - fd. 1/2" bar over remains of USGLO mon. - placed 6' x 6" x 36" conc. mon.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

fd. pavement box with U.S.F.S. conc. mon. with five (5) accessories listed in Rowe Eng. survey and corner recordation (1991 and 1992) in Liber 252, P. 387-8 and L. 2 C.R.C., P. 14 as recited below in C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

pavement box with USFS conc. mon.

- references: Carsonite post / West / 25.00 ft
power pole / S 33°W / 114.20 ft
22" w. pine / N 75°W / 30.80 ft
power pole / N 54°E / 70.70 ft
24" sugar maple / S 40°E / 50.10 ft



SIGNED BY [Signature] DATE 9-8-97 SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.