

MAR 03 2000

# LAND CORNER RECORDATION CERTIFICATE

SECTION

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

1999 Alcona County Remonumentation

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25N N. S., R. 5E E. W.	E-10
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County  
Remonumentation  
Book 2 Page 26

Filed for Record in  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 12-17-1999 At 10:32  
LAND CORNER 9.00

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on Dec. 8 1999, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-10: 1845: GLO sur. by J. Mullett - set post and referenced
- 1931: dep. mesur. by G. Veal - set 6" x 24" conc. mon. w brass tablet
- 1973: sur. by R. Miller - fd. GLO mon. w brass tablet
- 1975: sur. by N. Caldwell - no description of corner
- 1995: sur. by D. MacNeill - fd. conc. mon. w brass tablet
- 1998: sur. by NE Land Surveys - no description of corner

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-10: found 6" conc. mon. w brass tablet and two of 1931 sur. witnesses

no evidence recovered from GLO sur. of 1845

distances and alignment are compatable with surveys of 1931, 1973, 1975, 1995 and 1998. accepted as the correct location for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10: 6" x 24" conc. mon. w brass tablet referenced:

- 14" ash / North / 58.65' to nail
- 3" conc. mon. / South / 59.50'
- pow. pole / N 75°E / 37.31' to nail
- pow. pole / N 73°W / 58.73' to nail
- (from 1931 sur.) fence cor. E, W & S / S 28°W / 64.0 to center

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY


Date 11/30/99  
County Rep. J.F.O.

SIGNED BY \_\_\_\_\_ DATE Dec. 8, 1999  
John F. Oliver  
SURVEYOR'S MICHIGAN REGISTRATION NO. 19840

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_