

SURVEY & REMONUMENTATION

MAR 04 1998

LAND CORNER RECORDATION CERTIFICATE SECTION

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

1997 Alcona County Remonumentation

APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY

Date 7/24/97 County Rep. [Signature]

RECORDED

Date: September 8, 1997 REMON LIBER 1 PAGE 262

2:20 Time P M

[Signature] Doris A. Gauthier REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

Table with columns: FOR CORNERS OF--, LOCATED IN--, CORNER CODE NUMBER. Rows include PUBLIC LAND SURVEY, PROPERTY CONTROLLING IN SECTION, MISCELLANEOUS PROPERTY IN SECTION, LOT NO., PRIVATE CLAIMS.

John F. Oliver

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above... established, re-established, monumented, re-monumented, recovered or restored...

A. Description of original monument and accessories and/or subsequent restoration:

- 1845: G.L.O. - set post and referenced
1914: A. Freer - gun barrel - 38" long
1933: Dependent resurvey - fd. iron bar 1 x 1 x 18 ins. - placed 6" x 24" conc. mon. with brass tablet


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

fd. Dependent resurvey conc. mon. with one (1) accessory 8" cedar / S 18°W / 44.90 ft

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

corner is 6" x 24" conc. mon. with brass tablet

- references: 8" cedar / S 18°W / 44.90 ft
8" cedar / S 45°W / 49.03 ft
10" cedar / N 65°E / 12.52 ft
Carsonite post / South / 0.5 ft



SIGNED BY [Signature] DATE 9-8-97

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____ CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____ MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____