

RF

MAR 03 2000

# LAND CORNER RECORDATION CERTIFICATE

## SECTION

### FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

1999 Alcona County Remonumentation

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T.25N N. S., R. 6E E. W.	B-3
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County  
Remonumentation  
Liber 2 Page 17

0  
Filed for Record in:  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 12-17-1999 At 10:32 am  
LAND CORNER 9.00

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on Dec. 8, 1999 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-3: 1845: GLO survey by J. Mullett - set post and referenced
- 1914: sur. by A. Freer - cor. is gray boulder 16 x 10 x 7 glass under
- 1983: sur. by USFS, J. Williams - cor. is brass capped conc. mon.
- 1993: sur. by NE land survey - cor. is called GLO monument

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY

Date 11/30/99

County Rep. D.J. B.C.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-3: found 6" x 6" conc. mon. with brass cap 51 feet North of centerline of gravel road with 4 of 1983 survey witnesses
- no evidence recovered from GLO survey of 1845
- distance and alignment are compatible with surveys of 1983 and 1993
- accepted as the correct location for the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-3: 6" x 6" conc. monument with brass cap 51 ft North of centerline of gravel county road referenced:

- (USFS sur.) 5" r. pine / S 60°E / 25.73' to exist. nail
- (USFS sur.) 8" maple / N 60°W / 34.05' to exist. nail
- (USFS sur.) 3" maple / North / 23.00' to exist. nail
- cedar post / North / 2.10' to center


SIGNED BY John F. Oliver DATE Dec. 8, 1999

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_