

SURVEY & REMONUMENTATION

APR 25 1995

**1994 ALCONA COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

COMMISSION

For corners in

Alcona
(County)

Located In:

Alcona County
Remonumentation
Liber 111
Page 111

Date: RECORDED
County Rep 3-10-95
E.T.L.
MAR 10 11 22 AM '95

- | | | | |
|------------------------------------|--------------|-------------|------------|
| 1. Public Land Survey | T <u>25N</u> | R <u>6E</u> | |
| | T _____ | R _____ | |
| | T _____ | R _____ | |
| | T _____ | R _____ | <u>B-6</u> |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

James A. ...
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	●	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Duane R. MacNeill, in a field survey on August 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| 1844 - Not set by original Government Surveyors | 1970's - 1990's - Other Surveyors into Caldwell's survey point. |
| 1968 - Surveyor, N. Caldwell sets 3/4" pipe at location purported to be center of section. | 1984 - Surveyor, Robert Griffin does sectional breakdown of Section 7 North of Section 18 and establishes 1/4 corner common to said Sections. |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Caldwell's corner is disallowed and the center of Section is established at the intersection of a straight line between A-6 and C-6 and a straight line between B-5 and B-7; which in the North-South direction is on the centerline of a new Bituminous Road, but is 13.89 feet West of Caldwell's 3/4" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Remonumentation Crew sets 1/2" re-rod in monument box. An Alcona County Brass cap, appropriately stamped, was secured to the 1/2" re-rod and witnessed.

Witnesses:

- | | | |
|----------|-------|-------------|
| N50°W | 58.05 | Power Pole |
| S45°W | 56.00 | 16" Maple |
| S30°W | 80.11 | 12" W. Pine |
| S15°W | 94.85 | 10" Spruce |
| Due East | 13.89 | 3/4" pipe |

Signed by

Duane R. MacNeill

Date December 28, 1994

Surveyor's Michigan License No. 19237

