

MAR 03 2000

LAND CORNER RECORDATION CERTIFICATE

SECTION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

1999 Alcona County Remonumentation

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>25N</u> N. S., R. <u>6E</u> E. W.	C-1
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County
 Remonumentation
 Liber 2 Page 20

Filed for Record in
 ALCONA COUNTY MICHIGAN
 DORIS A GAUTHIER
 On 12-17-1999 At 10:32 am
 LAND CORNER 9.00

REGISTER OF DEEDS STAMP AND
 FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Dec. 8, 1999, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-1: 1845: GLO survey by J. Mullett - set post and referenced
- 1901: sur. by E. Chapelle - cedar stake 4 x 4
- 1953: survey by MDOT - cor. shown East of M-65 - not identified
- 1983: survey by USFS, J. Williams - cor. is 5" x 60" conc. mon. with brass cap


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-1: fd. 5" x 5" conc. mon. with brass cap with another conc. mon. with brass cap 20.10 feet West
- no evidence recovered from GLO survey of 1845
- distances and alignment are compatible with MDOT Plans and 1983 USFS survey.
- accepted as the correct location for the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1: 5" x 5" conc. mon. with brass cap referenced:
- 5" w. pine / S 55°E / 14.51' to nail
- 14" w. pine / S 05°E / 18.90' to nail
- cedar post / South / 1.80 to center
- conc. mon. / N 85°W / 20.11'

APPROVED LAND CORNER
 P A 345 of 1990
 ALCONA COUNTY
 Date 11/30/99
 County Rep. [Signature]



SIGNED BY John F. Oliver DATE Dec. 8, 1999

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____