

MAR 03 2000

LAND CORNER RECORDATION CERTIFICATE

SECTION

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

1999 Alcona County Remonumentation

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25N N. S., R. 6E E. W.	C-2
2. PROPERTY CONTROLLING IN SECTION	, T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County
Remonumentation
Liber 2 Page 19

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-17-1999 At 10:32 a.m.
LAND CORNER 9.00

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Dec. 8, 1999, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-2: 1845: GLO survey by J. Mullett - set post and referenced
- 1901: sur. by E. Chapelle - no description of corner
- 1953: sur. by MDOT - cor. shown 6.22' East of centerline on plans
- 1983: sur. by USFS, J. Williams - corner is 1" iron bar in mon. box
- 1999: sur. by J. Oliver - fd. pav't. box with 1" iron bar

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date: 11/30/99
J.F. Oliver

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-2: fd. 1" iron bar in pavement box 6.22' East of centerline
- no evidence recovered from GLO survey of 1845
- distances and alignment are compatible with MDOT Plans, USFS survey and J. Oliver surveys
- accepted as the correct location for the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-2: placed 1/2" bar with brass cap along the side of the 1" bar in pavement box
- referenced:

- (USFS sur.) cedar post / N 88°E / 58.65' to center
- 18" elm / N 38°E / 83.25' to nail
- 15" elm / S 60°W / 57.93' to nail
- 5" triple apple / N 60°W / 67.00' to nail



SIGNED BY *[Signature]* DATE Dec. 8, 1999
John F. Oliver
 SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____