

SURVEY & REMONUMENTATION

APR 25 1995

1994 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED LAND CORNER

P A 345 of 1990
ALCONA COUNTY

Date RECORDED

County Rep E T L

Mar 10 10 22 AM '95

David A. Smith
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

For corners in

Alcona
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 25N | R | 6E | E-6 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Alcona County
Remonumentation
Page 1

I, Duane R. MacNeill, in a field survey on August 30, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|---|--|
| 1844 - Cedar Post set by Government Surveyor | 1901 - Surveyor, W.L. Chapelle found 10" x 11" stone marked with "X". | 1914 - Surveyor Andrew Freer finds 2 4" long iron. |
|--|---|--|

Witnesses:

HEM 18 N29°W 19
HEM 12 N58°E 11

No Witnesses

No Witnesses

- | | |
|---|--|
| 1956 - State Highway Surveyor finds pin. (No Witnesses) | 1984 - Surveyor D.R. MacNeill finds iron pin. (No Witnesses) |
|---|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2 " re-rod and confirmed its location with surveys from State Highway Department and Supervisor's Plat of Village of Glennie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Remonumentation Crew finds 1/2" re-rod and placed monument box. An Alcona County Brass Cap, appropriately stamped, was secured to the re-rod and witnessed.

Witnesses

- | | | |
|-------|-------|-------------------|
| N55°W | 95.15 | Power Pole |
| S45°W | 60.52 | Power Pole |
| S45°E | 58.34 | Power Pole |
| N10°E | 35.16 | S.W. Corner Bldg. |

Signed by

Duane R. MacNeill
DUANE R. MAC NEILL
REGISTERED LAND SURVEYOR
19237

Date December 28, 1994

Surveyor's Michigan License No. 19237