

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona
(County)

Located In:

Corner Code #

RECORDED

- 1. Public Land Survey T 25N R 6E
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

K-8

APPROVED LAND CORNER
P.A. 345 of 1990
ALCONA COUNTY

Date 7-21-95
County Rep. E.T.L.

JUL 21 2 12 PM '95

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, David B. Guthrie in a field survey on May 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1844: G.L.O. Survey by J.H. Mullett - Set post and referenced Beech 14 - N56E - 16 / Beech 6 - N83W - 17
- 1904: Survey by Edw. Chapelle - Cedar Post
- 1909: Survey by Andrew J. Freer - Grey boulder 14 x 12 x 11 inches
- 1959: Survey by R.S. Scott Eng. Co. - Set Railroad spike
- 1989: Survey by D.R. MacNeill and Assoc. - Set 1" Pipe
- 1993: Survey by D.R. MacNeill and Assoc. - Found 1" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found Iron Spike on the centerline of Hoskins Road to the East and 2.5 Ft. West of the centerline of Ford Road.

SURVEY &
REMONUMENTATION

OCT 26 1995

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: Set a 1/2" x 24" Iron Rod with a brass cap stamped to identify the corner placed in a monument box.
- Referenced: N50°E - Fe. Cor. Post - 49.78 Feet
- S45°E - Fe. Cor. Post - 47.18 Feet
- West - Fe. Cor. Post - 36.85 Feet
- S65°E - 12" Aspen - 74.91 Feet



Signed by D.B. Guthrie

Date 7/21/95

Surveyor's Michigan License No. 22435