

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in Alcona (County) Located In: _____ Corner Code # _____

- 1. Public Land Survey T 25N R 6E
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

K-11

APPROVED LAND CORNER
P.A. 345 of 1990
ALCONA COUNTY
Date 7-21-95
County Rep ETL

JUL 21 2 13 PM '95

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

I, David B. Guthrie in a field survey on May 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1844: G.L.O. Survey by J.H. Mullett - Set post and referenced Y.Pine 24 - S59E - 50 / Y.Pine 24 - S44W - 24
- 1904: Survey by Edw. Chapelle - Flat grey limestone 2 1/2 x 19 x 24
- 1959: Survey by R.S. Scott Eng. Co. - Set Railroad spike
- 1967: Survey by R.S. Scott Eng. Co. - Found Railroad spike
- 1977: Survey by James Campbell - R.R. spike
- 1986: Survey by William E. Woods - Found 3/4" Iron Bar
- 1987: Survey by Ledy Eng. and Sur. - Found Railroad spike, set Concrete post 5" x 5" x 36" with brass tablet.
- 1993: Survey by D.R. MacNeill and Assoc. - Found brass tablet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1995: Found 5" x 5" Concrete post with brass tablet.

SURVEY &
REMONUMENTATION

OCT 26 1995

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: Set a 1/2" x 18" Iron Rod with a brass cap stamped to identify the corner directly over the 5" x 5" Concrete post with a brass cap placed in a monument box.
Referenced: S82°E - Utility Pole - 33.96 Feet
S38°W - Utility Pole - 89.12 Feet
S72°W - Proj. Marker (face) - 79.75 Feet
N31°W - 4" Spruce - 118.23 Feet

Signed by *D.B. Guthrie*

Date 7/21/95

Surveyor's Michigan License No. 22435

