

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 25N R 6E  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

L-7

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY

Date: 7-21-95  
County Rep. E. J. L.

RECORDED

JUL 21 2 13 PM '95

*Doris A. Benthien*  
REGISTER OF DEEDS  
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		1
5											
6	18		17		16		15		14		1
7											
8	19		20		21		22		23		2
9											
10	30		29		28		27		26		3
11											
12	31		32		33		34		35		3
13											

I, David B. Guthrie a field surveyor on May 23, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1844: G.L.O. Survey by J.H. Mullett - Set post and referenced Beech 8 - N42E - 11 / Beech 6 - S74E - 30

1959: Survey by R.S. Scott Eng. Co. - Set Railroad Spike

1989: Survey by D.R. MacNeill and Assoc. - Found 1" Pin

1993: Survey by D.R. MacNeill and Assoc. - Found 1" Pin

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 1" Iron Pin

SURVEY & REMONUMENTATION

OCT 26 1995

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set a 1/2" x 24" Iron Rod with a brass cap stamped to identify the corner placed in a monument box.

- Referenced: N30°E - 10" W.Pine - 91.10 Feet
- N62°W - 15" Maple - 83.72 Feet
- S23°E - 6" Spruce - 62.35 Feet
- S50°E - 15" W.Pine - 90.65 Feet



Signed by

*D.B. Guthrie*

Date

7/21/95

Surveyor's Michigan License No.

22435