

1995 Alcona County Remonumentation Corner

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY

Date: 7-21-95  
County Rep. E.T.L.  
RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alcona (County) Located In: Corner Code #

1. Public Land Survey	T <u>25N</u> R <u>6E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Alcona County Remonumentation  
Liber 21 Page 95  
131  
JUL 21 2 14 PM '95

*David A. Guthrie*  
REGISTER OF DEEDS  
ALCONA COUNTY MICHIGAN

Alcona County Remonumentation Liber Page

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

I, David B. Guthrie in a field survey on June 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced Y.Pine 16 - N75W - 66
- 1967: Survey by R.S. Scott Eng. Co. - Found 1927 Gov't Cor.
- 1989: Survey by D.R. MacNeill and Assoc. - Found monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1995: Found 1" Iron Pipe with brass cap.

SURVEY & REMONUMENTATION

OCT 26 1995

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: 1" Iron Pipe with brass cap stamped to identify the corner.  
Referenced: S20°E - 12" R.Pine - 36.06 Feet  
S16°W - 8" R.Pine - 30.30 Feet  
N72°E - 10" Jack Pine - 53.63 Feet  
N22°W - 10" Oak - 45.91 Feet  
North - 3/4" Iron Pipe - 33.00 Feet



Signed by David B. Guthrie Date 7/21/95

Surveyor's Michigan License No. 22435