

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in Alcona (County)

Located In:

Corner Code #

- 1. Public Land Survey T 25N R 6E
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 Date 7-21-95
 County Rep. E.T.L.

JUL 21 2 13 PM '95

David B. Guthrie
 REGISTER OF DEEDS
 ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

I, David B. Guthrie on a field survey on May 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced Beech 14 - S22W - 56 / W.Pine 28 - N73W - 55
- 1828: Dependent Resurvey by Guy R. Veal - Set concrete monument with brass cap.
- 1959: Survey by R.S. Scott Eng. Co. - Set Railroad Spike
- 1986: Survey by Ledy Eng. and Sur. - Found 6" x 6" Concrete post with brass cap 34 inches below the surface. Set Railroad spike and 1" Iron pin over the tablet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1995: Found 1" Iron Pin above a 6" x 6" Concrete post with a brass cap.

DAVID B. GUTHRIE
 SURVEY & REMONUMENTATION
 OCT 26 1995
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: Set a 1/2" x 18" Iron Rod with an aluminum cap stamped to identify the corner, directly over a 6" x 6" Concrete post with a brass cap.
 Referenced: N11°E - 10" Aspen - 27.56 Feet
 N31°E - 20" Twin Maple - 80.27 Feet
 S36°E - 15" Red Pine - 121.53 Feet
 N38°W - Utility Pole - 86.34 Feet

Signed by D.B. Guthrie

Date 7/21/95

Surveyor's Michigan License No. 22435

