

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in Alcona Located In: _____ Corner Code # _____
(County)

- 1. Public Land Survey T 25N R 6E
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

M-11
 APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 Date 7-21-95
 County Rep E. J. K.

JUL 21 2 15 PM '95

Janice A. Dunbar
REGISTRAR OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie on a field survey on June 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced Elm 10 - S60W - 32 / B.Alder 3 - N30W - 13
- 1928: Dependent Resurvey by Guy R. Veal - Set Iron post 3 ft. long, 2 ins. in dia. with brass cap.
- 1967: Survey by R.S. Scott Eng. Co. - Found 1927 Gov't Cor.
- 1986: Survey by Ledy Eng. and Sur. - Found Iron post 2" dia. with brass cap under surface of Beaver Pond.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 2" Iron Pipe with brass cap in old Beaver flooding.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: 2" Iron Pipe with brass cap stamped to identify the corner.
- Referenced: North - 1/2" Iron Rod - 141.15 Feet
- West - 1/2" Iron Rod - 87.11 Feet
- North - 20" Oak - 99.30 Feet
- S05°W - 1/2" Iron Rod - 41.95 Feet



Signed by D.B. Guthrie Date 7/21/95
Surveyor's Michigan License No. 22435