

1995 Alcona County Remonumentation Corner

Alcona County
Remonumentation
Liber 1 Page 13
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alcona (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>25N</u> R <u>6E</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

APPROVED LAND CORNER
 P. A. 345 of 1990
 ALCONA COUNTY
 Date 7-21-95
 County Rep. E.T.L.

JUL 21 2 14 PM '95

David A. Smith
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, David B. Guthrie in a field survey on June 2, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	18		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced Spr. Pine 6 - S57W - 25 / B.Oak 6 - N81W - 22
 - 1928: Dependent Resurvey by Guy R. Veal - Set iron post 3 ft. long, 2 ins. in dia. with brass cap.
 - 1967: Survey by R.S. Scott Eng. Co. - Set 3/4" Iron Pipe by single proportion between the S.E. and N.E. corners of Section 36.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1995: Found 3/4" Iron Pipe

ALCONA COUNTY
REMONUMENTATION
OCT 26 1995
COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1995: Set a 1/2" x 24" Iron Rod with an aluminum cap stamped to identify the corner 6" below the road surface.
Referenced: S84°W - 16" Oak - 60.90 Feet
N60°W - 4" Jack Pine - 60.10 Feet
N32°W - 4" R.Pine - 79.97 Feet
S32°W - 8" R.Pine - 93.94 Feet



Signed by D.B. Guthrie Date 7/21/95