

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in Alcona (County) Located In: Corner Code #

- 1. Public Land Survey T 25N R 6E
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Section S T R

M-13
APPROVED LAND CORNER
P.L.A. 345 of 1990
ALCONA COUNTY

JUL 21 2 14 PM '95

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, David B. Guthrie, on a field survey on June 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced Spr. Pine 6 - S54W - 41 / Spr. Pine 7 - N51E - 29
- 1928: Dependent Resurvey by Guy R. Veal - Set Concrete monument 6 x 6 x 36 in with brass tablet
- 1960: Survey by Earl Winn - Found Cement monument with brass cap
- 1967: Survey by R.S. Scott Eng. Co. - Found 1927 Gov't Cor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1995: Found Concrete post with brass cap.

SURVEY & REMONUMENTATION

OCT 26 1995

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: Concrete post with brass cap stamped to identify the corner.
- Referenced: S62°W - 7" Jack Pine - 63.38 Feet
- N45°W - 7" Jack Pine - 62.72 Feet
- N36°E - 4" Jack Pine - 33.33 Feet
- S45°W - 12" Jack Pine - 30.42 Feet
- N45°E - Wood Post - 33.70 Feet
- N48°W - Conc. Mon. - 63.78 Feet



Signed by

David B. Guthrie

Date

7/21/95

Surveyor's Michigan License No. 22435