

REMONUMENTATION

FEB 22 1996

COMMISSION

ALCONA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County Remonumentation Liber 1 Page 148

For corners in

ALCONA (County)

Located In:

Corner Code #

1. Public Land Survey

T25NR7E

G-1

T R

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

APPROVED LAND CORNER P.A. 345 of 1990 ALCONA COUNTY

Date County Rep. E.T.L.

RECORDED

DEC 20 4 43 PM '95

Janis A. Matthews

REGISTER OF DEEDS Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

WILLIAM E. WOODS in a field survey on 12-12-1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1844: JAMES MULLETT

SET POST

HEM 20" S69°W 36

CEDAR 18" S62°E 15

Grid table with columns A-L and rows 1-13. Cell G-1 is marked.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1911: IRON BOLT 32" LONG 1 1/4" DIAMETER WITH BUR ON TOP 2 1/2 X 2 1/2 SQUARE. SIX STONES DIFFERENT SIZES WITH BROKEN GLASS.

1928: INDEPENDENT RE SURVEY SET POST 2" X 36" WITH BRASS CAP. POPLAR, 5" DIAMETER S30°30'E., 95 LKS. (62.7) POPLAR 5" DIAMETER S30°15'W 79 LKS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995 REMONUMENTATION, WILLIAM E. WOODS P.S. 25882

USE 2" PIPE WITH BRASS CAP AS ESTABLISHED BY INDEPENDENT RE SURVEY.

30" POPLAR S30°E 60.67 WITH FOREST SERVICE PLATE

24" BALSAM S60°E 10.53

12" ASH N20°E 21.87

12" BALSAM S32°W 23.10

Signed by

William E Woods

Surveyor's Michigan License No.

25882

Date

12-20-95

