

REMONUMENTATION

FEB 22 1996

COMMISSION

ALCONA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALCONA  
(County)

Located in:

Corner Code #

1. Public Land Survey

T25NR 7E

I-1

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

APPROVED LAND CORNER  
P.A. 345 of 1990  
ALCONA COUNTY

Alcona County  
Remonumentation  
Liber 1 Page 150  
RECORDED  
Dec 20 4 43 PM '95  
*David A. Matthew*  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WILLIAM E. WOODS, in a field survey on 12-12- 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844: JAMES MULLETT

HEM 16" S10°W 27

BEECH 6" S63°E 23

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1911: ANDREW J. FREER

GRAY BOULDER 10 X 9 X 11 DIAMOND SHAPED GRANITE STONE 12 X 7 X ON TOP. ALSO THREE DRIFT BOLTS.

1928: INDEPENDENT RE SURVEY

SET AN IRON POST, 3 FT. LONG 2" DIAMETER. 27" IN THE GROUND FOR CLOSING CORNER OF SECTIONS 2 & 3 WITH BRASS CAP. ASH 3" DIAMETER BEARS S52°30'E. 176 LKS. POPLAR, 5" DIAMETER, BEARS S40°W 118 LKS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: REMONUMENTATION WILLIAM E. WOODS P.S. 25882

TO USE BRASS CAP ESTABLISHED BY INDEPENDENT RE SURVEY.

30" ASH N5°W 31.54

36" T.ASH S65°W 42.84

20" BIRCH WITH FOREST SERVICE MARKER. N75°W 13.64

24" W.PINE S76°E 93.23

Signed by William E Woods  
Surveyor's Michigan License No. 25882

Date 12-20-95

