

1997 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alcona (County)

Located In:

Corner

Alcona County Remonumentation
Liber 1 Page 228

- 1. Public Land Survey T 25N R 08E E07
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

APPROVED LAND CORNER
P.A. 345 of 1996
ALCONA COUNTY
Date: 8/13/97
County Rep. D. H. Lee

Aug 18 1 53 PM '97

James A. Heather
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Wayne T. Lewis, in a field survey on June 26, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: GLO Set post. Witnesses given: White Birch 10 N 27° E 22, White Birch 9 S 29° E 12.
- 1900: County Surveyor Set dark gray boulder 15x21 on top of crockery.
- 1973: Richard Miller, P.S. No monumentation or witnesses given.
- 1973: Richard Miller, P.S. Liber 1 CRC, page 58 - found nail in centerline of road, set 1/2" pipe. Witnesses given: S 24° E 68.35' Power Pole, S 38° W 51.55' Jack Pine, N 44°36' W 43.97' Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found 5" square concrete monument with brass cap indicating corner with #13584 (Robert A. Griffin).

SURVEY & REMONUMENTATION

MAR 04 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Accepted existing concrete monument and brass cap as an Alcona County Remonumentation marker.



- Witnesses given:
- N 45° W 44.25' Clump of Maple
 - N 20° W 55.95' 10" Jack Pine
 - S 40° W 51.30' Jack Pine Stump
 - S 60° W 60.88' 10" Jack Pine
 - N 45° E 46.46' 1/2" Rerod W/Cap #19840/25882

Signed by *Wayne T. Lewis*
Surveyor's Michigan License No. 41922

Date August 13, 1997