

1997 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alcona
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 25N R 08E
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 Date 7/21/97
 County Rep. *[Signature]*

RECORDED
 Alcona County
 Remonumentation
 Liber 100-10 Page 225
 AUG 13 1997 PM 4:37

[Signature]
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Wayne T. Lewis, in a field survey on June 26, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1843: GLO Set post. Witnesses given: Maple 8 N 30° E 21, Beech 10 N 88° E 38

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1997: Set 1/2" rered at single proportion measure between E-7 and E-9 and in centerline of North/South road and in line with fence to the East.

SURVEY & REMONUMENTATION

MAR 04 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1997: Placed appropriately stamped Alcona County Remonumentation 3" brass cap on set 1/2" rered in mon. box.

Witnesses given:
 East 34.02' Fence Corner
 S 30° E 59.35' 10" Aspen
 N 85° W 43.15' Power Pole
 N 40° W 148.00' 15" Maple



Signed by *Wayne T. Lewis* Date August 13, 1997
 Surveyor's Michigan License No. 41922