

**SURVEY &
REMONUMENTATION**

MAR 04 1998

1997 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 Liber 1 Page 230

Alcona County
Remonumentation

For corners in
Alcona
(County)

Located In:

Corner Case #

- | | | | | | |
|---------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>25N</u> | R | <u>08E</u> | <u>E09</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous
Property in Sec. | S | | T | R | |
| | S | | T | R | |

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 Date: 7/31/97
 County Rep. [Signature]

RECORDED

Aug 13 2 00 PM '97

[Signature]
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					

I, Wayne T. Lewis, in a field survey on June 26, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: GLO Set post. Witnesses given: White Pine 18 N 5° E 13, Cedar 8 S 18° W 8
 1903: County Surveyor Set iron post w/stone on top. Witnesses given: White Pine Stump 26 S 9° W 54, White Pine Stump 2 N 21° W 71-1/2
 1975: John Oliver, P.S. No monumentation or witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found pipe 6.9' West of road centerline to the North and South, and in the centerline of road to the East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed appropriately stamped Alcona County Remonumentation 3" brass cap on set 1/2" rerod next to existing pipe 6" below road surface.

Witnesses given:

- N 45° W 52.95' Power Pole
 S 45° E 53.35' 12" Aspen
 S 65° E 94.35' 6" Red Pine
 N 30° W 135.10' Southeast Corner of Garage



Signed by [Signature]
 Surveyor's Michigan License No. 41922

Date August 13, 1997