

1997 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County  
Remonumentation  
Liber 1 Page 225

For corners in  
Alcona  
(County)

Located In:

Corner Code

- 1. Public Land Survey T 25N R 08E
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ R \_\_\_\_\_

F07

APPROVED LAND CORNER  
P.A. 345 of 1990  
ALCONA COUNTY

Date 7/31/97  
County Rep W. Lewis

RECORDED

Aug 18 1 50 PM '97

*W. Lewis*  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F | G | H | I | J | K | L |
|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |   |   |   |   |   |   |   |

I, Wayne T. Lewis, in a field survey on June 26, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1843: GLO Set post. Witnesses Given: Cedar 6 S 2° E 22, Hemlock 18 N 35° E 16
  - 1900: County Surveyor Cedar post.
  - 1973: Richard Miller, P.S. No monumentation or witnesses given.
  - 1973: Richard Miller, P.S. Liber 1 CRC, page 58 - Set 3/8" rod w/cap midway in straight line. Witnesses given: Due North 33.0' 3/8" Rod, Due South 31.95' Fence Post, S 60° 30' W 12" Birch

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997: Found 1/2" rered midway and on line between E-7 and G-7. Corner falls 1' South of road centerline and 1' West of fence to the North.

**SURVEY & REMONUMENTATION**

MAR 04 1998

**SECTION**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1997: Placed appropriately stamped Alcona County Remonumentation 3" brass cap on 1/2" rered in place of existing 1/2" rered in mon. box.



- Witnesses given:
- N 25° W 43.82' 10" White Pine
  - N 60° E 69.80' 12" Aspen
  - S 25° W 55.36' 6" Balsam
  - S 70° W 76.60' Power Pole

Signed by *Wayne T. Lewis*  
Surveyor's Michigan License No. 41922

Date August 13, 1997