

REMONUMENTATION

FEB 22 1996

ALCONA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County  
Remonumentation  
Liber 1 Page 153

For corners in  
**COMMISSION**

ALCONA (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25NR8E</u>	G-7
	T <u>   </u> R <u>   </u>	_____
	T <u>   </u> R <u>   </u>	_____
	T <u>   </u> R <u>   </u>	_____
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	_____
	S <u>   </u> T <u>   </u> R <u>   </u>	_____
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	_____
	S <u>   </u> T <u>   </u> R <u>   </u>	_____

APPROVED BY THE BOARD OF PROFESSIONAL SURVEYORS  
MICHIGAN COUNTY REGISTER OF DEEDS  
Date Feb 2, 1996  
County Rep. F.T.L.

RECORDED  
FEB 14 4 43 PM '96

*Janis A. Gauthier*  
REGISTER OF DEEDS  
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WILLIAM E. WOODS in a field survey on 1-16-, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
1843: GOVERNMENT SURVEY SET POST W.PINE 20" S37°W 12  
HEM 12" N75°E 22

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
COUNTY SURVEY NBT. W.PINE STUMP 14" N28°E 34½  
W.PINE 20" S37°W 12  
1973: RICHARD L. MILLER FOUND 1" PIPE BELOW SURFACE. SET 3/8 ROD ABOVE  
EXISTING 1" PIPE. N71°17'E 36.42  
CLUSTER OF MAPLES S76°15'E 36.90 12" MAPLE TREE S56°45'W 72.52  
10" MAPLE TREE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1995: REMONUMENTATION WILLIAM E. WOODS P.S. 25882  
1/2" BAR WITH ALUMINUM CAP IN MONUMENT BOX.  
36" CLUSTER MAPLE N75°E 36.39 12" MAPLE S70°E 37.02  
8" TRIPLE MAPLE S78°W 117.93 P.P. #1493 N68°W 413.98



Signed by William E Woods  
Surveyor's Michigan License No. 25882

Date 1-30-96