

REMONUMENTATION

FEB 22 1996

COMMISSION

ALCONA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
Remonumentation
Liber 1 Page 161

For corners in

ALCONA (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25</u> R <u>8</u>	H-3
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

APPROVED LAND CORNER
P.A. 345 of 1990
ALCONA COUNTY
Date 2-1-96
County Rep E.T.L.

RECORDED

FEB 1 4 42 PM '96

Jane A. Santier
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, WILLIAM E. WOODS in a field survey on 1 16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3								●					
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
1843: GOVERNMENT SURVEY

FIR 12" S42°E 17
TAM 12" N34°E 12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1992: NORTHEAST LAND SURVEYS
BILL WOODS

FOUND 1" PIPE. NO WITNESSES
AT S. 1/4 ALSO FOUND 1" PIPE.
1/8 CORNER MIDWAY AND ON LINE
WITH S.E. SEC. CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: REMONUMENTATION WILLIAM E. WOODS P.S. 25882
SET 5/8" ROD BY 48" IN LENGTH WITH ALUMINUM CAP.

12" ASH N56°W 15.45
12" ASH S25°E 61.81

10" ASH S47°W
CEDAR POST EAST



Signed by William E Woods
Surveyor's Michigan License No. 25882

Date 1-30-96