

SURVEY & REMONUMENTATION

1997 Alcona County Remonumentation

SECTION

For corners in Alcona (County)

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74 Mich. P.A. 1970

Alcona County Remonumentation

Number 1 Page 231

RECORDED

AUG 16 2 00 PM '97

David S. Hetherington
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 25N R 08E | R09 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

APPROVED LAND CORNER
P.A. 345 of 1990
ALCONA COUNTY

Date: 7/21/97
County Rep: D. S. Hetherington

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

I, Wayne T. Lewis, in a field survey on June 26, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: GLO Set post. Witnesses given: Cedar 9 N 65° E 11, Cedar 10 S 44° E 22
County Surveyor Witnesses given: White Pine Stump 22 S 11-1/2° W 48, White Pine Stump 30 N 7-1/2° E 59
- 1973: James Campbell, P.S. 1" Pipe. Witnesses given: N 30° W 65.03' Power Pole, S 05° W 39.25' Power Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found 1/2" rerod 4' South of road centerline and 1.5' West of fence to the North

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed appropriately stamped Alcona County Remonumentation 3" brass cap on existing 1/2" rerod in box.

- Witnesses given:
S 60° W 94.15' 12" White Pine
S 03° W 34.70' Power Pole
North 33.00' 1/2" Rerod W/Cap #19840/25882
N 25° W 70.90' Power Pole
N 10° W 87.15' 8" Cedar



Signed by *Wayne T. Lewis* Date August 13, 1997
Surveyor's Michigan License No. 41922