

RECORDED

1997 Alcona County Remonumentation

Alcona County  
LAND CORNER RECORDATION CERTIFICATE Remonumentation  
Filing Requirement of Act 74, Mich. P.A. 1970  
Page 222

For corners in  
Alcona

(County)

Located In:

Corner Code

- 1. Public Land Survey T 25N R 08E I09
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

APPROVED LAND CORNER  
P.A. 345 of 1990  
ALCONA COUNTY

Date: 11/31/97  
County Rep: [Signature]

RECORDED

AUG 18 1 57 PM '97

Register of Deeds Stamp & File Number

[Signature]  
REGISTER OF DEEDS

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Wayne T. Lewis, in a field survey on June 26, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1843: GLO Set post. Witnesses given: Maple 8 N 56° E 15, Maple 8 S 47° E 25  
County Surveyor Witnesses given: White Pine Stump 36 N 29° E 56-1/2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997: Found 1/2" rered in intersection of road.

SURVEY &  
REMONUMENTATION

MAR 04 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1997: Placed appropriately stamped Alcona County Remonumentation 3" brass cap on existing 1/2" rered in non box.

- Witnesses given:
- N 30° E 68.20' Power Pole Stump (found tag #22435)
  - N 30° E 68.90' Power Pole
  - N 15° E 122.70' 5" Red Pine
  - S 45° W 43.21' Fence Post (found tag #22435)
  - S 40° E 56.86' Power Pole (found tag #22435)
  - N 70° E 87.05' 6" White Pine



Signed by [Signature]

Date August 13, 1997

Surveyor's Michigan License No. 41922