

1997 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County  
Remonumentation  
Liber        Page 227

For corners in  
Alcona  
(County)

Located In:

Corner Code =

- |                                    |   |     |   |     |     |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey              | T | 25N | R | 08E | J09 |
|                                    | T |     | R |     |     |
|                                    | T |     | R |     |     |
|                                    | T |     | R |     |     |
| 2. Property Controlling in Section | S |     | T | R   |     |
|                                    | S |     | T | R   |     |
| 3. Miscellaneous Property in Sec.  | S |     | T | R   |     |
|                                    | S |     | T | R   |     |

APPROVED LAND CORNER  
P.A. 345 of 1990  
ALCONA COUNTY

Date: 7/31/97  
County Rep. W.R.C.

RECORDED

Aug 18 1 58 PM '97

*Denis A. Bantler*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Wayne T. Lewis, in a field survey on June 26, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1843: GLO Set Post. Witnesses given: Hemlock 6 S 19° W 10, Hemlock 8 S 52° E 13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997: Found 1/2" rerod w/cap unidentifiable, 3.1' North of road centerline

**SURVEY & REMONUMENTATION**

MAR 04 1998

**SECTION**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1997: Placed appropriately stamped Alcona County Remonumentation 3" brass cap on existing 1/2" rerod in mon. box.

- Witnesses given:  
S 05° W 40.10' Fence Corner  
S 45° W 62.45' 8" Aspen  
S 10° W 113.40' 8" Maple  
N 05° W 35.28' Fence Post (found tag #22435)



Signed by *Wayne T. Lewis* Date August 13, 1997  
Surveyor's Michigan License No. 41922