

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

1998 Alcona County Remonumentation

Table with 3 columns: FOR CORNERS OF--, LOCATED IN--, CORNER CODE NUMBER. Includes rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY

Date 9/22/98 County Rep [Signature]

Filed for Record in ALCONA COUNTY MICHIGAN DORIS A GAUTHIER On 10-21-1998 At 11:21:40 LAND CORNER 9.00 OR

REGISTER OF DEEDS STAMP AND FILING NUMBER

Alcona County Remonumentation Page 307


SURVEY & REMONUMENTATION NOV 25 1998

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above... established, re-established, monumented, re-monumented, recovered or restored as expressed below...

- A. Description of original monument and accessories and/or subsequent restoration: K-7; 1843: GLO survey by J. Mullett - set post and referenced 1956: survey by MDOT for M-171 Hwy. - cor. is shown 0.74 ft W. of c/1 1970: survey by E. Ostling for Plat Lazy W Ranch Est. - shown as POB for Plat - no description of corner 1978: survey by NE Surveys - shown as found monument box 1990: survey by D. MacNeill - shown as found monument box 1993: survey by NE Surveys - shown as found monument box

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: K-7; found pavement box with 1/2" rod and cap distances and alignment are compatible to MDOT date from 1956 Plans. Accepted as the correct location for the corner. no evidence recovered from GLO survey of 1843

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: K-7; placed brass cap on 1/2" rod in the pavement box referenced: pow. pole / S 70°E / 74.02 ft 5" w. Birch / S 53°E / 88.64 ft 13" w. Pine / S 75°W / 73.90 ft 16" w. Pine / S 42°W / 112.53 ft



SIGNED BY [Signature] John F. Oliver DATE Oct. 6, 1998 SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES: SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____ APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)