

1997 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74 Mich. P.A. 1970

Alcona County Remonumentation
Liber 1 Page 223

For corners in
Alcona
(County)

Located In:

Corner Code

- 1. Public Land Survey T 25N R 08E K-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

APPROVED LAND CORNER
P.A. 345 of 1980
ALCONA COUNTY
Date: 7/31/97
County Rep: W.T.L.

RECORDED

AUG 18 1 57 PM '97

Denis A. Heather
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Wayne T. Lewis, in a field survey on June 26, 1997
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1843: GLO Set post. Wit. given: Beech 6 S 53° E 13, Beech 6 S 24° W 17
 - 1901: County Surveyor Wit. given: W Pine Stump 30 S 18° E 53, W Pine Stump 40 N 50° W 96-1/2

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1997: Found 1/2" rod w/cap #22435 in mon box 2.8' East of road centerline, and in line with fence to the East and road centerline to the West.

SURVEY & REMONUMENTATION

MAR 04 1998

SECTION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1997: Placed appropriately stamped Alcona County Remonumentation 3" brass cap on existing 1/2" rod in mon. box.



- Witnesses given:
- S 65° W 85.76' Power Pole
 - S 50° W 77.10' NE Corner Concrete Pad for GTE Equipment
 - N 40° W 86.40' Power Pole
 - East 58.35' Fence Corner

Signed by *Wayne T. Lewis*

Date August 13, 1997

Surveyor's Michigan License No. 41922