

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

1998 Alcona County Remonumentation

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25N N. S., R. 8E E. W.	K-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

APPROVED LAND CORNER
FORM 1990
ALCONA COUNTY

Date 9/22/98
County Map D.M. Cur

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 10-21-1998 At 11:21:59 am
LAND CORNER 9.00
OR

REGISTER OF DEEDS STAMP AND
FILING NUMBER

Alcona County Remonumentation Liber Page 305

**SURVEY &
REMONUMENTATION**

NOV 25 1998

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Oct. 2, 1998, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-12; 1843: GLO survey by J. Mullett - set post and referenced
- 1903: survey by E. Chapelle - post - no witnesses
- 1956: survey by MDOT for M-171 Hwy. - no cor. shown on plans
- 1982: survey by NE Surveys - fd. R.R. spike - no witnesses

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- K-12; corner placed on line between K-13 and K-11 at fence lines East and West as shown on MDOT Plans from 1956 AND 441.00 ft North of survey recorded in L. 189, p. 888.

no evidence recovered from GLO survey of 1843

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-12; set 1/2" bar and brass cap in a pavement box referenced:

- pow. pole / N 85°W / 56.67 ft
- 6" Maple / S 45°E / 169.75 ft
- 8" Maple / S 73°E / 97.39 ft
- 6" tw. Maple / N 45°E / 146.02 ft



SIGNED BY John F. Oliver DATE Oct. 7, 1998
SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____