

REMONUMENTATION

DEC 16 1996

1996 Alcona County Remonumentation Commission Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County Remonumentation Liber 1 Page 170

Table with columns: For corners in Alcona (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

APPROVED LAND CORNER P.A. 345 of 1990 ALCONA COUNTY Date 9-20-96 County Rep. E.T.L. REGISTERED SEP 24 2 41 PM '96 REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, David B. Guthrie in a field survey on July 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced Beech 8 - S19W - 40 / Beech 9 - S43W - 47
1903: Survey by Edw. Chapelle - Beech 24 - S53W - 40
1994: Survey by Lewis and Lewis - Found 1/2" Iron Rod Referenced: N65E - Anchor Pole - 17.39 Feet, N49W - Utility Pole - 52.15 Feet, S66E - 36" Maple - 27.52 Feet, S18E - 12" Basswood - 43.31 Feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Found 1/2" Iron Rod with cap #27452 at the intersection of a North South road and fencelines East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Set a 1/2" x 24" Iron Rod with an Aluminum Cap stamped to identify the corner 6" below the road surface. Referenced: N65°E - Anchor Pole - 17.39 Feet, N49°W - Utility Pole - 52.15 Feet, S66°E - 36" Maple - 27.52 Feet, S18°E - 12" Basswood - 43.31 Feet



Signed by [Signature] Date Sept. 17, 1996
Surveyor's Michigan License No. 22435