

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF --: | LOCATED IN --: | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>25</u> N. R. <u>8</u> E. <input checked="" type="checkbox"/> | I-6; I-7 |
| 2. PROPERTY CONTROLLING IN SECTION <u>15</u> | T. <u>25</u> N. R. <u>8</u> E. <input checked="" type="checkbox"/> | 14 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. R. _____ E. <input type="checkbox"/> | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

Alcona

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 12, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-6 Found 2" pipe 5'± below road surface raised to 6" below surface with 1" pipe.
- I-7 Set corner from probable U.S.B.T. hemlock stump. Fits measurement and line north, south, and west.
- 14 Set by standard survey procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| I-6 | I-7 | 14 |
|---------------------------|-------------------------------|----------------------|
| 2½' of 1" pipe | Set DNR monument & cedar post | Set 2½' of 1" pipe |
| 5" cedar N80°W 50.7 | 4" W. Pine S70°W 15.3 | 8" cedar S51°W 25.3 |
| Twn. 8" Maples S10°W 25.3 | Twn. 8" Balsam N04°W 43.0 | 9" cedar N70°W 35.2 |
| | | Pine River North 3'± |

SIGNED BY Kenneth J. Ostling DATE 6
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)