

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

✓

LAND CORNER RECORD

T. 25. NR. 8 E.

Alcona

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 18 and 19.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER

Notch in 2 1/2" W. Pine -	N4W	-	127 1/2 links
6" Balsam	-	S12E	- 111 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division Land Surveyor while making a survey of Section 19. Could not identify anything for government BTe- no other sign of corner. Corner falls about 3.5' north of E-W fence on north side of road.

Corner placed and witnessed April 26, 1960.

SURVEYORS SEAL

SIGNED *Kenneth Ostling*
REGISTERED LAND SURVEYOR

DATE 4/28/60