

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25. NR. 8 E.

Alcona

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19-20-29-30

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

18" R. Pine	-	N80W	-	103 links
20" R. Pine	-	N15W	-	128 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division Land surveyor while making a survey of Section 19. Found old post in place, and very old stake bottom below surface. Fence constructed to this point from east. Falls in line with centerline of road between Sections 20 and 29. This corner probably perpetuated the corner as found and restored by E. Chapelle in 1903 while making a survey for township road. Checks acceptably with stream east, and appears to be best available evidence of corner.

Corner was placed and witnessed April 27, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Osling*
REGISTERED LAND SURVEYOR

DATE 4/28/60