

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 25. NR. 8 E.

Alcona COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 17-18-19-20

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

20" R. Pine	-	S39E	-	6 links
16" R. Pine	-	N57E	-	59 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division Land Surveyor while making a survey of Section 19. Set corner at fence intersection-- old fences north, south and west, and falls in line with township road east. This location appears to have been accepted as the corner, and can find nothing to the contrary. Seems best available evidence of the proper location for the corner.

Corner was placed and witnessed April 26, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE 4/28/60