MICHIGAN DEPARTMENT OF CONSERVATION

FORESTRY DIVISION

CORNER 25 8E T_24 NR_9E----RECORD

	AlconaIosco COUNTY
DESCRIPTION OF CORNER	Section corner common to Sections 6,1,31,36
DESCRIPTION OF CORNER	MONUMENT 1" pipe, with 4" brass cap 6" below surface
WITNESSES TO CORNER .	
	NE corner of building foundation S40E 88 links
	18" R. Pine - N58W - 126 links
	8" W. Birch - N37E - 120 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial resurvey of T25N R9E. Could find no record of a previous survey, and all government evidence gone. Established corner in centerline of road intersection. This point conforms almost exactly with stream about 9 chains east, road has been maintained by county and occupied to, an old brush line goes south from this point and a cabin SW of the intersection appears to have been built relative to the road intersection. This point is on line over corners to the east, and makes the S line of Section 31 short of record but this condition exists throughout the entire SW 1/4 of this township. The distance west to the river bluff and river is about 80 links longer than record, but did not believe this warranted upsetting the apparent equities established by occupation. It would seem that one might assume the road was constructed to some evidence of a survey which in turn disappeared during construction.

Corner placed and witnessed May 7, 1958.

SURVEYOR'S SEAL

SIGNED Trunch & Other DATE 6/5/58
REGISTERED LAND SURVEYOR J