

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ²⁵₂₅ NR. ^{8E}_{9E}

Alcona COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 25, 36, 30, 31

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap - 4" below surface

WITNESSES TO CORNER

18" R. Pine - S85W - 55½ links

6" Aspen - N35E - 64½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement on a direct line between W 1/4 corner Sec. 31 and the corner to Sections 18 and 19. Could not identify original BT's, nor any previous survey. Corner is in center of county road.

Section corner record for 1/4 between 31 and 36 for more information.

Corner placed and witnessed May 7, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*
REGISTERED LAND SURVEYOR

DATE 6/5/58