

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

25 9E
T. 25. NR 8E

Alcona COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19, 30, 24, 25 . . .

DESCRIPTION OF CORNER MONUMENT 1" x 24" pipe, only driven below surface of road

WITNESSES TO CORNER

Power pole - S51E - 77 links

Corner fence post S68W - 41 links

Corner is 4 links west of apparent centerline of present grade and 18 links north of fence lines.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between corner of 18 and 19 north and W 1/4 corner of 31 south, on direct line. See corner record for 1/4 between 31 and 36 for more information. Corner is 18 links north of fence lines west and east, but fence east bears to north, making it fairly good in latitude of the W 1/8 corner between 19 and 30. This position makes the S 1/2 mile of Sec. 19 equal to the N 1/2, and checks the 1/4 line fence of Sec. 19.

Corner placed and witnessed May 7, 1958

SURVEYORS SEAL

SIGNED *Kenneth J. Otterley*
REGISTERED LAND SURVEYOR

DATE 6/5/58