

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 25 NR 8 E
T 25 NR 9 E

Alcona COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 34 and 36

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

12" R. Pine	-	N 28 W	122 1/2 links
20" R. Pine	-	N 56 E	83 links
Corner fence post		S 78 W	43 links

Corner is in center of N-S road, 6 links north of a fence line that bears S87W.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Could locate no previously established corners on the west boundary south of the corner to Sections 18, 19, 13, 24. Corner was established in center of county maintained road for longitude, at proportionate measurement between the town corner south and the corner to Sections 19 and 18 north. A deflection of 1° 21' to the east is apparent at this corner. However, in view of the fact that the road is straight for 3 1/2 miles going north, and bears N0° 04' W by solar observation, and since this road has been intermittently fenced and occupied to, and no other evidence of a previous survey could be found, it seemed justifiable to consider the road as the best available evidence as to the proper location of this corner and the others in the 2 1/2 miles going north. The deflection at this corner was left as noted, since it seemed unreasonable to set all corners up to 50 links east of the road and make the miles east any shorter than they are.

SURVEYORS SEAL Corner was placed and witnessed May 7, 1953.

SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE 5/7/53