

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

25 9E
T. 24. NR. 9E

Alcona - Iosco COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 5,6,31,32

DESCRIPTION OF CORNER MONUMENT Left 1" pipe in place and took witnesses

WITNESSES TO CORNER

8" W. Pine - S4W - 181 links

7" W. Pine - N4E - 167 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found 1" pipe previously established by unknown surveyor. This corner has been used in staking property in Iosco County and conforms fairly well with the government record to the stream east. Although the lengths of the 2 miles east and 1 mile west are made inconsistent, this corner was one of the few found to exist, and since it appeared to have been used in previous surveys, was accepted as valid in our survey. Found evidence of an old line running north from this corner for 1/4 mile.

Corner placed and witnessed May 7, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Wetling* DATE 5/23/58
REGISTERED LAND SURVEYOR