



MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T...²⁵₂₄ NR...^{9E}_{9E}...

Alcona - Iosco COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3,4,33,34

DESCRIPTION OF CORNER MONUMENT Left 3/4" pipe in place and took witnesses

WITNESSES TO CORNER

10" R. Oak - N41E - 141 1/2 links

5" Ash - N38W - 99 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew. Found 3/4" pipe set previously by unknown surveyor. Check okay with swamp edge 1 chain west, and exactly with Freer's record to centerline of county road 9 rods east. Also checks acceptably with shore of lake east. Corner was used as control for other corners on county line west.

Corner placed and witnessed May 7, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 5/29/58
REGISTERED LAND SURVEYOR