

**SURVEY &
REMONUMENTATION**

DEC 1 6 1996

1996 Alcona County Remonumentation Corner

**Alcona County
Remonumentation
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 Liber 1 Page 167

For corners in <u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>8E</u>	<u>M-2</u>
	T <u>25N</u> R <u>9E</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

SEP 24 2 41 PM '96

David B. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

APPROVED
P.A. 345 of 1990
ALCONA COUNTY

Date 9-20-96
County Rep E. J. L.

I, David B. Guthrie in a field survey on July 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:**
- 1837: G.L.O. Survey by Lewis Clason - Set Post and Refernced
Tam. 10 - S11W 16 / Tam. 8 - N76W - 44
 - 1903: Survey by Edw. Chapelle - Post
Spr 10 - S42W - 74 / Spr 10 - N341/2E - 41
 - 1976: Survey by Northeast Land Surveys - Liber 163, Page 175.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**
- 1996: Found 1/2" Iron Rod at Road intersection.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- 1996: Set a 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.
Referenced : N26°E - 10" Ash - 96.37 Feet
S35°E - 6" Maple - 104.40 Feet
S55°E - Utility Pole - 70.50 Feet
N82°E - 10" W. Pine - 105.80 Feet



Signed by *D.B. Guthrie* Date Sept. 20, 1996