

2000 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alcona  
(County)

1. Public Land Survey	Located In: T 25N R 09E	Corner Code # C-2	✓
	T R		
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

Alcona County Remonumentation  
Liber 2 Page 88

Filed for Record in  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 09-20-2000 At 09:54 am.  
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Wayne T. Lewis, in a field survey on 3-30-2000, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	•	5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
1843 - James A. Mullet: Used 15" Yellow Pine for post, no witnesses given  
1890 - County Surveyor: Set boulder and broken glass for corner and witnessed  
1977 - Richard L. Miller, P.S.: Found nothing, and set 3/4" pipe w/cap in intersection of roads, and recorded LCRC (L 1, P 59), and witnessed  
1993 - Northeast Land Surveys: Found Pavement Box, no witnesses given  
1999 - John F. Oliver, P.S.: Found pavement box, no witnesses given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found pipe w/cap (unreadable) in mon box, 3' East of road to North, in line with roads to South and East and West. Mon box damaged during recovery and will be replaced.

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
Date 9-6-2000  
County Rep. W.T.L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
2000 - Placed 3" Alcona County cap, stamped to identify the corner, on 1/2" rered driven next to pipe in mon. box

- Witnesses:
- N 40° E 44.40' Guy Pole (set tag #41922)
  - S 55° E 56.28' Power Pole (set tag #41922)
  - S 40° W 44.71' Power Pole (set tag #41922)
  - N 70° W 90.48' 10" Twin Maple (set tag #41922)
  - N 50° W 55.37' Wood Fence Corner Post (set tag #41922)



Signed by [Signature]  
Surveyor's Michigan License No. 41922

Date September 14, 2000

SURVEY & REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1985

FEB 07 2001

SECTION